617

CHITALDRUG DIVISION.

Dated January 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 6th February 1919, for constructing Police Station and Lines at Kottige,, Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Police Station and Lines at Kottige, Holalkere Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

Abstract estimate for constructing Police Station and lines for one Dafedar and 3 Constables at Kottige, Holalkere Taluk, Chitaldrug District:—

Serial No.	Items of work	Per	Total quantity
1	Earthwork excavation in gravelly soil for foundation and filling in basement ...	C. yd.	127
2	Burnt stone in clay foundation and basement	C. ft.	4,647
3	Burnt brick in clay superstructure	„	3,924
4	Burnt brick in mortar	„	1,944
5	Burnt brick coping with chunam plastering	R. ft.	67
6	Burnt stone slabs 6" thick dressed nicely	S. ft.	606
7	Teakwood lock-up doors with iron bars clamps, etc.	„	49
8	Honnewood battened doors with iron clamps, etc	„	440
9	Honnewood windows battened with iron clamps, etc.	Sq. ft.	71
10	Honnewood ventilators with iron bars expanded metal, etc.	„	11
11	Honnewood battened ventilators with battened iron bars, etc., complete ...	S. ft.	16
12	Honnewood work wrought and put up	C. ft.	129·24
13	Roofing with 1st class Mangalore tiles over teakwood reepers	Sq.	28·37
14	Ridge tiles set in mortar	R. ft.	87
15	Chunam borders over the roof	„	109
16	Teakwood ceiling below rafters for lock up-rooms	Sq. ft.	210
17	Chunam plastering	Sq.	106·5
18	White and colourwashing 2 coats	„	110·69
19	Honnewood eaveboards	R. ft.	392
20	Wood oiling to wood work two coats	Sq.	12·74
21	Tarring wood work 2 coats	„	3·00
22	Teakwood railings as per plan	R. ft.	52
23	Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing	Sq.	9·64
24	Flooring with Cuddapah slabs over 3" concrete bed and cement pointing ...	„	5·12
25	Teakwood gate with iron clamps, bolts, hinges, etc., complete	S. ft.	16
26	Silicate painting 2 coats	Sq.	17.71
27	Constructing "V" shaped drains to lead off water with concrete and cement pointing.	R. ft.	100
28	Flooring with gravel including watering and tamping	C. yd.	20
29	Teakwood finials	Each	4
30	Teakwood pendents	„	8
31	Cutting groves and dressing stone pillars	„	2
32	Constructing seats in latrine and fixing drain pipes	Lump sum Rs.	(No. 5 latrines).
33	Clearing site and levelling ground	Lump sum	Rs.
34	Providing chimney over kitchen for smoke escape ... m ...	Each	4
35	Providing 1½" galvanised iron pipe to drain water from latrine and kitchen ...	„	8
36	Constructing cistern in kitchen	Lump sum	Rs. (No. 5).
37	Providing pestle and mortar stones	Lump sum	Rs. (No. 4).
38	Chunam pointing	Sq.	4·41
39	Tarring walls of latrine and woodwork imbeded in walls	Lump sum	Rs.
40	Coping with burnt brick in chunam over compound wall and latrine including plastering, etc., complete.	R. ft.	152

N. G. KRISHNA IYENGAR,
Executive Engineer.